There are four domestic versions of the 7160:

- 1. 7160-A Used in -31W-1 paralled printer (10 pitch) 2200/VS
  - L1, 2, 3, 4, and R8 not loaded
  - L11 = 378-0517, L13 = 378-2041
  - Jumper A-B/D-E/F-G/N-P/U-V/X-Y
- 2. 7160-1A Used in a -31W-2 paralled printer (12.pitch) 2200VS
  - L15, 16, 24, 25, and R12-19 not loaded
  - L11 = 378-0517, L13 = 378-2041
  - Jumper A-B/D-E/F-G/N-P/U-V/X-Y 2200 -
- 3. 7160-D Used in a -31W-1 serial printer (10 pitch) VS/WP
  - L1, 2, 3, 4, and R8 not loaded
  - -L11 = 378-0521 (R2), L13 378-2050 (R2)
  - Jumper A-C/F-H/J-K/N-P/V-W



WEEKLY COMPUTER TELEX #36 PG. 4

- 4. 7160-1D Used in a -31W-2 serial printer (12 pitch) VS/WP
  - L15, 16, 24, 25, and R12-19 not loaded.
  - L11 = 378-0521 (R2), L13 =  $3\overline{78}$ -2050 (R2)
  - Jumper A-C/F-H/J-K/N-P/V-W

PCB	2231W	••	2231V	. 5531
6756	NO CHANGE	NO C	NO CHANGE	NO CHANGE
6761	JUMPER A TO B and D TO F	, JUMP	JUMPER B TO C and E TO F	JUMPER B TO C and E TO F
0929	FOR MODEL 62	FOR	FOR MODEL 62	USE 7160-1D JUMPER A TO C, F TO G, J TO M N TO P, and U TO W
7060	FOR MODEL 61	FOR	FOR MODEL 61	USE 7160D JUMPERS SAME AS 7160-1D
KEYBOARD	USE 6762	USE	USE 67£2	USE 6762-1
CHASSIS	NO CHANGE	ON .	NO CHANGE	USE MODIFIED CHASSIS WITH CANNON CONNECTOR
				SEE WPNL #30 FOR ADDITIONAL INFORMATION

### 2231-1/-2 Underscore

To enable the underscore function on the 31W-1/-2 printer the following boards must be as stated below:


210-6761-Timing and Format Control Board for 10 and 12 Pitch E-REV level must be at least 4 up to latest, E-REV 9


210-7060-10 Pitch Data Storage, I/O Control and Char Generator Board E-REV level must be at least 3 up to latest, E-REV 7. Solder wire from L17 pin 9 to L27 pin 10

210-6760-12 Pitch Data Storage, I/O Control and Char Generator Board E-REV level must be at least 2 up to latest, E-REV 7. Solder wire from L17 pin 8 to L28 pin 10

Some new 31W printers are being sent out with 210-7160A boards for 10 pitch and 210-7160-1A for 12 pitch replacing the 7060 and 6760 respectively. If you have a problem with underscoring with these boards, try reverting back to the 7060 and 6760. The 7160A and the 7160-1A are universal boards for parallel printers for 2200 and VS and should be capable of underscoring. There are jumpers on the 7160A and 7160-1A which should be set as follows:

A to B, D to E, F to G, N to P, U to V, X to Y





ES



### TECHNICAL INFORMATION NOTICE

page 1 of 1

Date Issued:	April 17, 1984	Notice Number:	U\$.0U38-
Product:	VS/0S	Component/Version:	6.11.55
1			

5531-2 224651 5521

VS Operating System Individual Fix 6.11.55 (Uppercase)

This memo announces the availability of U.S. Individual fix version 6.11.55. It fixes two important problems affecting specific devices. Update 6.11.55 consist of one module:

DEVLIST Version 6.11.54 (Device Parameter file)

Update 6.11.55 includes the device support in updates 6.11.51 and 6.11.52, since DEVLIST 6.11.54 is a superset of DEVLIST versions 6.11.45 and 6.11.49. In addition, update 6.11.55 is compatible with all other 6.11.50 individual fixes. Therfore, you may overlay 6.11.55 on top of an unmodified 6.11.50 Operating System or on top of a 6.11 OS that contains any other individual fix (6.11.51 through 6.11.54). do not overlay 6.11.55 on any Operating System earlier than 6.11.50.

The 6.11.55 upoate will have no effect on the Operating System Version number which is displayed through "System Status" function of the Operator's Console screen.

Since these changes do not effect any workstation or printer microcode or any WP code, it does not have any foreign language dependencies.

### PROBLEMS FIXED:

- PROBE # F003978:
   5531-2 Printer did not print Lower case characters.
- 2. Informally Reported: Proper microcode was not being loaded to two Ideographic devices --2246Sl workstation and 552ll printer.

To receive this software you should contact your ATUM and he will request it from the CESS VS/PC/2200 Group.

Queries concerning this information should be referred to: C.E. Software Support

2231W3

### TOPIC: TOP OF FORM PROBLEM ON THE 2231W-3

The top of form problem that has been plaguing the 2231W-3 has been resolved. The problem was that the top of form would not always stop at the same distance from the top of form. Most customers primarily used the 2231W-3 as a graphics printer and the top of form problem is not usually noticed.

The problem is corrected by redesign of the 210-6794 PC board to incorporate a strobe pulse from the vertical format control unit along with a channel 7 strobe to stop the paper. In doing this, an addition to the board is required.

The way they differentiated between the new and old at first was to replace 210-6794 RO and 210-6794 Rl with 210-6794 R2 M3. The boards with R2 M3 on them caused problems in Logistics so they finally changed the board number to 210-7894.

A few boards with the number 210-6794 R2 M3 went to the field before the remainder were pulled from stock and re-numbered 210-7894. The old boards 210-6794 R0 and 210-6794 R1 are all to be scrapped.


When the 210-7894 (and the few 210-6794 R2 M3) boards are used in the 2231W-3, a new format control unit 279-5060-38 must also be used. The old format control unit 279-5060-29 does not have provision for the strobe channel. The new format control unit also plugs into the 210-7894 PC board, not into the chassis as the old unit did.

When ordering the new board 210-7894, the new format control unit 279-5060-38 should also be ordered.

FOR LITES ON PANEL BURNING OF

CONNECT 3 22012 RESILTOUR
FROM L 20, PINS 2,4,66
TO ± OV.

BACK OF (20 on 7060



Connect 3 REO OR CIRCLES PTS.

# Service Newsletter No. 54

PERIPHERALS #15


July 14, 1976

This Newsletter contains the following:


- A. MODEL 2231W PRINTER PROBLEM CORRECTIONS
- B. ASSEMBLY DIRECTIONS FOR WANG MODEL 61/62/72 PRINTER STANDS
- A. MODEL 2231W PRINTER PROBLEM CORRECTIONS

As a result of 2231W printer problem areas experienced by field service personnel, the following solutions are recommended.

- 1) PRINTER RIBBON EREAKING Ribbon cartridge was loaded with too much ribbon causing ribbon jams. Manufacturing has solved the problem by reducing length of ribbon loaded in cartridge.
- 2) PAPER CATCHING ON RIBBON & PRINTHEAD RIBBON GUIDE Perforations in paper catch on bottom of ribbon guide or ribbon as paper is advanced. The print head ribbon guide has been redesigned and can be ordered from the Home Office (WL #449-0131).
- 3) JERKING CARRIAGE MOVEMENT Excessive play between the main drive belt and the plate on the bottom of the carriage assembly may result in jerking carriage motion. An .010 shim of plastic or paper inserted between the belt and plate (spanning the entire length of the plate) will cure this problem.
- 4) SHIPPING BOLTS BROKEN THROUGH THE PLYWOOD BASE Future shipments will use thicker plywood base.



PAPER CATCHING ON PRINTHEAD RIBBON GUIDE



JERKING CARRIAGE MOVEMENT

- B. ASSEMBLY DIRECTIONS FOR WANG 61/62/72 PRINTER STANDS
- 1) Insert grommets (7) and bumpers (9) in leg stiffener (8) and modesty panel (3) respectively. The hole in the bumper should be on the indented side of the modesty panel.

>

- 2) Attach modesty panel (3) with slots for paper rack (10) on the bottom of the panel to vertical leg assemblies [vertical leg assembly consists of lower leg support (11) and vertical leg (1)] with allen head cap screw and black flat washer (2), the hole in the bumper (9) facing the back.
- 3) Place leg stiffener (8) on top of vertical leg assemblies and align the holes with the tapped holes in the vertical leg (1). The grommets (7) should be towards the back with the bend in the leg stiffener down.
- 4) Attach upper leg support (6) to the vertical leg through the holes in the leg stiffener with hex head stove bolts and split lock washers.
- 5) Insert the eight plugs into the spare screw holes (13) located in the front inside edges of the legs.
- 6) Place bumpers on input paper rack (12).
- 7) Place the tabs of the paper rack (10) in slots in the modesty panel allowing bumpers to rest against the bottom of the panel:
- 8) Put the hooked ends of the output paper rack (5) through the grommets (7) in the leg stiffener and place the ends of the paper rack lower support (4) in the bumpers (9) in the modesty panel.

FRONT -

## Service Newsletter

NO. 61

PERIPHERALS #17

This Newsletter contains the following:

- A. MODEL 2231W/120W PRINTER MOTHERBOARD
- B. 2231W I/O CABLE
- A. MODEL 2231W/120W PRINTER MOTHERBOARD

The Model 2231W motherboard (6757 PC) has been replaced by the 7157 PC motherboard. The new motherboard has two 44 pin connectors, instead of three 30 pin connectors, to allow the insertion of an RS-232 interface board (7077 PC).

The Model 120W printer also has a RS-232 I/O Dataphone connector mounted on the rear of the printer (in addition to the standard Wang I/O Amphenol connector). When the RS-232 Option is installed, the Wang I/O connector can still be used to operate the printer or to connect the printer exerciser. (See Figure 1.)

### B. 2231W I/O CABLE

The Model 2231W I/O cable is terminated on the printer end with a 90 degree strain relief connector to prevent the cable from interfering with paper movement. The I/O cable can be modified by replacing the standard connector cover with a 90 degree strain relief connector (WL #350-4231).

To prevent accidentally disconnecting I/O cable, a cable clamp is shipped on the I/O cable which should be mounted under the rear chassis mounting screw. This cable clamp (WL #654-1255) should be added to all 2231W matrix printers that have an I/O cable with a 90 degree strain relief connector. (See Figure 2.)




FIGURE 1 2231W PRINTER CHASSIS




FIGURE 2 2231W I/O CABLE CLAMP LOCATION

# Service Newsletter

NO. 7

November 3, 1976

### PERIPHERALS #20 MODEL 61/62 DIFFERENCES

This Newsletter documents the differences between the Model 61 Matrix Printer (10 pitch, marketed as Model 2231W1) and the Model 62 Matrix Printer (12 pitch, marketed as Model 2231W2).

There are only three parts which differ between the Model 61 and the Model 62 Matrix Printers. These parts are listed below:

PART	MODEL 61	MODEL 62
PRINTHEAD	279-5060-22	279-5060-12*
TIMING WHEEL	461-2020	461-2021
CHARACTER GEN PCB	210-7060	210-6760

\*The Model 62 (12 pitch) printhead has a dot punched on the face of the printhead bearing for identification purposes.

Except as listed below, all adjustments are the same for both models of the printer (refer to Section 5 of the MODEL 61 MATRIX PRINTER MAIN-TENANCE MANUAL).

- 5.2 (b) (1) WS ADJUSTMENT

  with the carriage moving in the forward direction, adjust

  R71 on the 6761 PCB to 1600 usec ±25 usec for the Model 61

  and to 1800 usec ±25 usec for the Model 62.
- 5.2 (b) (3) To properly phase the signals from the two magnetic reluctance pickups, pivot the mounting plate for the magnetic pickup that senses the index hole of the timing disk (Figure 5-17 in the manual) for a difference of 800 usec ±50 usec for the Model 61 and for a difference of 900 usec ±50 usec for Model 62. The signal timing difference is measured between the positive edge of the signal at L3 pin 12 and the positive edge of L3 pin 13. The positive edge of L3 pin 13 is used to trigger the scope sweep.

### CUSTOMER ENGINEERING TECHNICAL ASSISTANCE CENTER NEWSLETTER

#20112

III.C.4

PERIPHERALS-PRINTERS/PLOTTERS-WANG MATRIX 61/62 (31W).

IOPIC: 210-7160-Z: PROMS FOR 2231W PRINTER

210-7160-Z HAS THE LATEST ASCII PROMS. PROMS ARE L11=378-0630; L13=378-2522.

### CUSTOMER ENGINEERING TECHNICAL ASSISTANCE CENTER NEWSLETTER

#### #10804

### III.C.4

PERIPHERALS-PRINTERS/PLOTTERS-WANG MATRIX 61/62 (31W).

### TOPIC: TOP OF FORM PROBLEM ON THE 2231W-3

The top of form problem that has been plaguing the 2231 W-3 has been resolved. The problem was that the top of form would not always stop at the same distance from the top of form. Most customers primarily used the 2231 W-3 as a graphics printer and the top of form problem is not usually noticed.

The problem is corrected by redesign of the 210-6794 PC board to incorporate a strobe pulse from the vertical format control unit along with a channel 7 strobe to stop the paper. In doing this, an addition to the board is required.

The way they differentiated between the new and old at first was to replace 210-6794 RO and 210-6794 R1 with 210-6794 R2 M3. The boards with R2 M3 on them caused problems in Logistics so they finally changed the board number to 210-7894.

A few boards with the number 210-6794 R2 M3 went to the field before the remainder were pulled from stock and re-numbered 210-7894. The old boards 210-6794 R0 and 210-6794 R1 are all to be scrapped.

When the 210-7894 (and the few 210-6794 R2 M3) boards are used in the 2231W-3, a new format control unit 279-5060-38 must also be used. The old format control unit 279-5060-29 does not have provision for the strobe channel. The new format control unit also plugs into the 210-7894 PC board not into the chassis as the old unit did.

When ordering the new board 210-7894 the new format control unit 279-5060-38 should also be ordered.

### CUSTOMER ENGINEERING TECHNICAL ASSISTANCE CENTER NEWSLETTER

### #20330

### III.C.4 PERIPHERALS-PRINTERS/PLOTTERS-WANG MATRIX 61/62 (31W).

### TOPIC - DEFAULT VALUE FOR 2231W-3\_LINE\_COUNT\_PER\_PAGE

Switch settings for 31W-3 printers for lines per page on the 210-6795 I/O data storage & character generator are as follows:

### Switch #'s on. all others off Approximate lines per page

5, 4, 3, 2 All OFF 5	50 53 56
4	61
5. 4 6 lines per inch	66
3	72
5, 3	80
4.3 8 lines per inch.	88
5, 4, 3	100
2	112
5, 2	132
4, 2	156
5, 4, 2	198
3, 2	260
5, 3, 2	370
4, 3, 2	704

Switch one is not acting in either position. The above chart was developed by changing the switch bank one, configuration on the 210-6795 PCA in the 2231W-3; using an MVP as central processor. Some of the high density lines overlap so much that they may vary several lines from the published number of lines. But, 6 lines per inch, and 8 lines per inch are exact values, for a standard 11" vertical printer form. Once the SW bank 1 is set, it will retain this default line count on all printed lines except when using the vertical format tape, or software statement hex (O9xx) XX = number of times 1/72 of an inch per line feed. XX may vary from (1 to 15) = "O1 to "OF". All subsequent lines (not VFU or software controlled) will default to the LPI default value as set above on the switch bank. So if a customer wants other than the default value, he will have to software control each line.

NEW TO - MAIN - AIN A 2231 W-3 1N ABOITIN 5 PARES USED ON 2231W-1-2 TO 1. EA. 1. I/O DATA STORAGE AND PROM CHARACTER GENERATOR P.C.B. REMARKS E 7060 HEN ENARACTES SET PA 1. EA. 2. TIMING AND FORMAT CONTROL 210-6714 RUSTACCS EGDS1 REPIRCES 210-6751 1 EA, 3. 2231-W-3 PROM ON 10 15420 372-2154 CHARACTER SCT I FA. 4. VERNIER AND PORMAT ASSEMBLY 279-5 224- 5060-37 5. MOTOR AND PULLEY ASSY, (P.F) 279-506-REPLACES 279-5060-37 1 EA. 6. HEAD ASSY (-61) (6635-51) 279-19. REPLACES 279-5060-22 1 EA. 7. CARRIAGE MOTOR + ENCEDER ASSY 229- 5050 REPLACES 279-5060-15 I EA. 8. BELT (STEP MOTOR TO CLUSTER PULLE 656-023 1 En. 9. BELT ( VERNICE TO CLUSTER PULLIN IEA. 10. PLATE ASSY CLUSTER PULLEY . -;

```
J. Hilliam
ARE OF NEW MACHINE:
MODEL 63 PRINTER-PLOTTER, (SAME AS
  ..... THE PRESENT MODEL 62 EXCEPT AS
   .... FOLLOWS:
EN PARTS:
                                    478-0377 (1 READ)
   20 TOOTH, .080 PITCH PULLEY, (SING. NO. B6636-405)
  GETS PINNED TO PAPER FEED MOTOR SHAFT, REPLACES
   THE 15 PITCH, INTOUTH PULLEY. 1 P. S. P. C51-1509
                                PENNING SERVING IMPORTS MY
                                STEVE STORY AL DROWNING
 CLUSTER 10LER PULLEY (DWG. 10. 86636-402) (1854,2)
   82 TOOTH, .080" PITCH, 3/16.188 WIDE BELT (IREGO)
                               656-0234
   60 TOOTH, 1/5 PITCH, .188 WIDE BELT (120XL) (1RE 70)
REPLACES BELT THAT GOES FROM VERVIER PULLET TO PAPER FOLD
650-0221
                     216 TOOTH, 80 MITCH, 14/2 P.A. (1REGU)
  ENCODER SEAR
  (0WG NO. C6636-197) (PLACES PRESENT 10 a 12 PITCH GEAR)
(15 DOW ON ECN)
  STUD, CLUSTER PULLEY MTG (DWG NO. 86636-403) (1 REGD)
FRANCE DESCRIEN
                                279-50 60 -80
  PLATE, CLUSTER PULLEY STUD MTG (OWG. NO. C6636-404) (IREGO)
```

B45 NEEDLE BRGS, PRESS INTO CLUTER PULLEY (2 REGD) RETAINING . RING 5133-25 (1 READ) TRU MAG.

ADD THO (2) #8-32 THRED NOWES TO FORMAT CONTINCE MTG. BRKT. (IS NOW ON ECN) (DUG. UG. DGG36-134) 452-0044

....

### PRODUCT SERVICE NOTICE

DATE: 4/1/81		III C 4 - 2
CLASSIFICA	ATION <u>Peripherals</u>	
С	ATEGORY Printer/Plotters	
	OUCT/APPL. Wang Matrix Pr	l l
	SEQUENCE <sup>#</sup> _1	
TITLE:	PRINTER HEAD SHIELD INSTA	LLATION PROCEDURE

#### I. INTRODUCTION

A new printer head shield (WLI #452-3575) has been designed to prevent smudge marks on multi-sheet forms printed on Wang Matrix Printers 2231W-1, 2231W-2, 2231W-3 and 2231W-6. Multi-sheet forms having as many as six sheets maximum thickness 0.02 inches (0.05 mm) are used in these printers. For the print wire to imprint on the final sheet the printer head must be adjusted as close as possible to the striker plate. This causes the small section of ribbon surrounding the printer head bearing to rub against the printing surface. As the printer head moves back and forth a smudge mark forms across the face of the document.

These smudge marks can be eliminated by installing a new printer head assembly (see section 2.0 for WLI#) with an attached head shield. The head shield becomes a barrier between the paper and ribbon, preventing the ribbon from rubbing the printing surface. A small round hole in the shield is aligned with the print wires allowing them to strike the ribbon.


The head shield will not be factory installed, instead all new printer heads will be modified to accept head shields. Head shield installation will be required only when a problem is detected.

### II. PARTS REQUIRED

PART NAME	MODEL NO.	PART NO.
Printer Head Assembly	2231W-1	WLI #279-5060-22
Printer Head Assembly	2231W-2	WLI #279-5060-12
Printer Head Assembly	2231W-3	WLI #279-5060-59
Printer Head Assembly	2231 <b>W-</b> 6	WLI #279-5060-88
Two 4-40 X 1/4 Phillips- head screws	All Models	WLI #650-2087
Printer Head Shield	All Models	WLI #452-3575

### III. PRINTER HEAD SHIELD INSTALLATION PROCEDURE

- 1. Power-down printer.
- 2. Lift open printer cover.
- 3. Remove ribbon cartridge as described in section 3.3.1, of the Matrix Printer Manual (03-0077, III.C.4) for models 2231W-1, -2 and -3. For the 2231W-6 Matrix Printer see section 2.6 of the 2231W-6 Matrix Printer Manual.
- 4. Remove existing print head assembly from carriage assembly by unplugging fingerboard from connector and removing the two mounting screws holding printer head assembly to carriage assembly (see Figure 1). Save the two mounting screws for installing the new printer head.



### FIGURE 1

5. Using two  $4-40 \times 1/4$  Phillips-head screws attach the printer head shield to the bottom of new printer head assembly (see Figure 2).

### NOTE

Each new printer head assembly is easily identified by its underside which has two drilled holes for mounting the printer head shield.




FIGURE 2

- 6. Install new printer head assembly on carriage assembly by plugging fingerboard into connector and attaching it to carriage assembly.

  Use the two mounting screws removed from the existing printer head (see Figure 1).
- 7. Adjust printer head assembly so the printer head shield is flush against the print head bearing (see Figure 2).
- 8. Refer to Matrix Printer Maintenance Manual (729-0339, III.C.4) and perform STRIKER PLATE AND PLATEN BRACKET ADJUSTMENT (paragraph 5.3.3) and PRINTER HEAD ADJUSTMENT (paragraph 5.3.5) on models 2231W-1,-2 and -3. For the 2231W-6 Matrix Printer refer to model 2231W-6 Matrix Printer Manual (729-0340, III.C.4) and perform STRIKER PLATE AND PLATEN BRACKET ADJUSTMENT (paragraph 6.3.6) and PRINTER HEAD ADJUSTMENT (paragraph 6.3.10).

#### NOTE

After performing the STRIKER PLATE AND PLATEN BRACKET ADJUSTMENT verify that a 0.013 in. ±0.001 in. (0.33mm ±0.25mm) clearence exists between the striker plate and head shield. Use the gauge (WLI #726-9487) that is supplied in the Customer Engineering Standard Tool Kit to check this measurement.

9. Using a multi-sheet form, perform the diagnostics in paragraph 7.2 of the 2231W-6 Matrix Printer Maintenance Manual (729-0340, III.C.4). These diagnostics enables the Print Consistency Test to be performed on the 2231W-1, -2, -3 and -6 Matrix Printers, thus, verifying that the head shield has corrected the smudging problem.



T0:

ALL CUSTOMER ENGINEERS

FROM:

JOE McDERMOTT, EASTERN AREA

DATE:

MAY 1, 1979

SUBJECT:

2231W-6 FAILURES

The numerous problems that have been encountered in the field with the 2231W-6 are being corrected through recent ECN's. These problems encompass intermittent deselecting of printer, frequent burning of servo fuse, excessive 7379 failure, unit line feeding and beeping when reset from keyboard, intermittent loss of data when printing, and excessive solenoid failures.

The following ECN's should rectify all the above problems. All ECN's should be done in order to eliminate any possibility of other design problems. In addition to the ECN's the new type of solenoid called Chamfered should be used when replacing solenoids. These solenoids have a much longer printing life than previous solenoids. The part number is still 279-5060-14.

If there are any questions concerning the 2231W-6 and the recent changes, please let me know.

· Regards,

JOE McDERMOTT

EASTERN AREA TECHNICAL SPECIALIST

JM:rb #2646A

cc: A.T.O.M.'s

ľ	MIZA NIC	•
\	WANG	J


# ECN

ECN	N	0.	140	3
SHEET 1 2	F /			

SHEET 1 OF /
DATE 4-24-79
RFA NO. (REF)

ス					_			RFA	NO. (REF			
	ORIGINATOR Robin Lo		DEPT.	15		EXT	3012		_DATE	4/	18/79	
	MODEL NO		TITLE								·	
M	PART 210-7333-A & -1A	PART						REV.	P.C. R	EV.	ELEC.	REV.
9	NO.	NAME	12 So	lenoi	id Memo	ry			FROM			
4	DWG. 7333 NO.	(DWG. TITLE)									•	-
	ASSY.	ASSY.	<del></del>	-			<u>-</u>		<u> </u>	EFF	ECTED	
	PART NO.	TITLE								NO	EFFECT	0
z .	DESCRIPTION OF CHANGE											
NO.		٠		•								
	Change schematic, softw	are load	ding ch	art a	ind BOM	as fo	ollows:			•		
	FROM		TO ·								•	
	378-4002-R6		378-4	002-R	7						•	
	378-4003-R6		378-4				Qty rea	mains	the sa	me ·		
	378-4004-R6 378-4005-R6		378-40 378-40									
	3/8-4003-R0		3/0-4	JUJ-K	.,							
ļ	No other documentation	changes	require	ed	•							
												ı
	•											
	•						Dr					
l					•		Κt	ECEIVE	בט			I
	·						APR	251	979			}
ı			•						•			]
L							PRIN	T ROO	DM			
	REASON FOR CHANGE		•									
İ												.
- 1	To correct mic speed switch r		error th	nat c	aused p	orinte	r to blo	ow fus	es and	fas	t	
i	Sheen switch t	eshouse										Ī
ł			•							•		ı
- 1	2969J/49									4	\$ 50	<b>)</b>
	NEW PURCHASE REQ'D.	SHOP	REWORK	REQ'	D.		VENDO	OR REW	ORK RE	Q'D.	<u> </u>	
•	CUSTOMER ENGINEERING		NOWLED	GE	×.		47001/01					$\Box$
	CUST. PER NEXT CALL D INFORMATION ONLY	BY:_   DATE		<del></del>			ATORY CH MENTATIO		NGE (PL.	вом	. DWG)	Į i
L	O NONE	<u> </u>			, i i	EASE (	OF MFG., C	COST RI	EDUCTIO		•	ŀ
ľ	DISPOSITION REPORT ASSA	SUB ASSY AREA	PARTS  N Outside  ouse Vendor	Future MFG.	[ ]	PRODU	JCT IMPRO	OVEME	NT			
	USE AS IS TO PREVIOUS REV.				FINAL APPROV	AL _	S 18.7	<i>4</i> υ				
T,	TO CONFORM X X	X		X	APPROV DESIGN		Robi	12	5,8	2.1	<u>-i</u>	
_		<u> </u>		1	APPROV MFG. EN				D. P.		4	9
<b> </b> E	TO CONFORM IF NOT BEYOND OP! RATIONS EFFECTED				WRITTEN		A mil	Re	hen		1.7	

	P. VVAIVG			ingreen I	£.			121 T	CE	# /	160	0	ATE.	1/0F_ 	<u> 2-7°</u>	7	
1	ORIGINATOR Ric	hard -G	Therr	ian		DEPT. TITLE		5	EX	кт	3019			DATE_		/27 /75	9
7 27	PART 209-7332 NO. 7332 NO. ASSY.			PART NAME (DWO TITLE	E 1 S. S.	12 <sub>.</sub> So	1 CPI	:				R F	EV.	P.C. F FROM	EFF	4 ECTE	A TC
HC.	DESCRIPTION OF CH Change artwork		embly	TITLE drai		and s	chem	natio	; per	etta	ched	prin	it —	· sec !		EFFEC	T 🖸
	Change BOM as													pe	di		
	Change: Add:	330 330	IL# )-101 )-304 )-190	7-4B						10 4.7	Ohm F K Ohm uf (	les Res					٠
					,	:				F		, RE	ECEI	VED			•
		•		٠.			٠					APR ARA	•	1379 Com			
•	REASON FOR CHANG	<b>E</b>	To g	jive :	seled	t F/I	- cir	rcuit	t more	e noi	ise i	mmuni	ty			· ·	
	NEW PURCHASE REQ	D.	0	SH	OP RE	WORK	REQ'	D.	•	0	VEN	DOR F	REWO	ORK RE	QʻD.	99	
	CUSTOMER ENC DIMMEDIATE CUST. DICUST. PER NEXT CA DINFORMATION ONL' DINONE	LL	ING	j BY	: TE:	WLED	<del></del>	( t	DC EA	SE O	F MFG.	TION C ., COST	HAN FREI	GE (PL.		, DWG)	
	DISPOSITION	Bonded	FINAL ASSY AREA	SUB ASSY AREA	IN House	RTS Outside Vendor	Future MFG.	1	) PR	ODUC	CT IMP	ROVE	MEN'	T	•	•	
	USE AS IS TO PREVIOUS REV. ••						·	APPE	ROVAL		·K.		) 5				
	TO CONFORM.					·	X	DES	GN ENG		11.911	ا أر مر	VV			c	P
	TO CONFORM IF NOT BEYOND OFFRATIONS								ENGRO	15	11:0	<del>یز برا</del>	`	<u> </u>	1	<u></u>	



(WANG)		SHEET 1 OF 1
		DATE <u>4-09-79</u> RFA NO. (REF)
ORIGINATOR S K Ho	DEPT. 15 EXT. 3000	DATE 4/4/79
MODEL NO. 2231W-6	TITLE :	
O NO.	PART NAME 12 Sol PS Regulator	REV. P.C.REV. ELEC.RE
DWG. 7379 NO. ASSY.	(DWG. TITLE)	0
PART NO.	ASSY. TITLE	NO EFFECT [
DESCRIPTION OF CHANGE	•	
Change artwork, assembly	drawing and schematic as follows:	
	etween Q2 emitter and +18V etween Q3 emitter and -32V	
Change BOM as follows:		
WL#	QTY DESCRIP	TION
Add: 334-0017	. 2 .25 Ohm	3W Res .
	· ·	
	•	•
		•
	4°,	
		•
NOTE: To affect all 2231	l series	
REASON FOR CHANGE		
	o prevent transistor burnout of Q2 o prevent high failure rate in fie	
2877J/47	# 60 PE - 1	
NEW PURCHASE REQ'D. □	SHOP REWORK REO'D.	NDOR REWORK REQ'D.
CUSTOMER ENGINEERING O JMMEDIATE CUST. A CUST. PER NEXT CALL O INFORMATION ONLY O NONE	"[ ] EASE OF MF	ATION CHANGE (PL, BOM, DWG) G., COST REDUCTION
DISPOSITION NOITISOGRID	PARTS SU IN Outside SU I PRODUCT IN	APROVEMENT

PARTS IN Outside House Vendor

FINAL APPROVAL

APPROVED DESIGN ENGRG.

APPROVED MFG. ENGRG.

WRITTEN BY

USE AS IS TO PREVIOUS REV.

TO CONFORM

TO CONFORM IF NOT BEYOND OPFRATIONS



USE AS IS TO PREVIOUS REV.

TO CONFORM

TO CONFORM IF NOT BEYOND OF RATIONS

## ECN

FCIA	140.11
SHEET 1 2	F
DATE	
	ספכו

		220000				RFA NO. (	REF)
	ORIGINATOR Dick Therris	n .	DEPT	15	_EXT	3019 DAT	e4/2/79
	PART 209-7332 NO DWG. D 7332 NO	PART . NAME (DWG TITLE)	12 Soleno	oid CP			C.REV. ELEC.REDM TO FROM TO
	ASSY PART NO.	ASSY. TITLE				•	NO EFFECT (
EC. NO	DESCRIPTION OF CHANGE		a and colo		200 2112	thad againt	
	Change artwork, assembl	y orawin	g and sche	matic (	per attac	ned print	
	Change BOM as follows:					•	
	VL#		QTY		DESC	RIPTION	
	Change: 330-20 Add: 300-10		from 2 to	3		Ohm 1/4W Res f Cer Cap	
	·. ·				·		
	••						
		•					
R	EASON FOR CHANGE	<del></del>		<del> </del>	······································		
		To improv	ve the pri	nter's	noise im	munity	•
	2852J/47	`				•	;
NI	EW PURCHASE REO'D	SHOP RE	WORK REQ	D.		ENDOR REWORK R	Q'D.
	CUSTOMER ENGINEERING () IMMEDIATE CUST. () CUST. PER NEXT CALL () INFORMATION ONLY () NONE	BY: DATE:	WLEDGE	X	DOCUMEN' EASE OF M	RY CHANGE FATION CHANGE (PL FG., COST REDUCT)	
DIS	Bonded ASSY AREA	SSE IN	Outside 25	[ ]	PRODUCT I	MPROVEMENT	


FINAL APPROVAL

APPROVED MFG. ENGRG.


WHITTEN BY

APPROVED DESIGN ENGRG. Predant This was

.



VVAIVG	•,				Y .	DATE			
ORIGINATOR Dick T	<u>herria</u> 6	n .	DEPT TITLE_	15 EXT. 12 Sol Printe	3019 er	<del>}</del>	DATE_		18/79
PART 209-7332 NO.		PART NAME		enoid CPU		REV.	P.C. R		ELEC.I FROM
DWG. 7332 NO		(DWG.		l ·			-	1,-	6
ASSY. PART NO.		ASSY. TITLE	·			•			CTED FFECT
DESCRIPTION OF CHANG	E							:	
Change artwork, as	sembly	/ drawin	g and so	hematic per at	tached pr	int ar	id as 1	follo	ws:
l) Add filte interrupt		cuit as	shown in	attached sket	ch, to no	n-mask	able	•	. <b>.</b>
2) Delete Sw	-2								
3) Change L2	3 from	74LS14	to 7414			•			•
Change BOM per att	ached	Sheet		•			•		: .
· · · · · · · · · · · · · · · · · · ·									•
_								٠.	
					_			•	
				,			•		•*•
•								<b>:</b> .	· ·
·	77.1	i				·		<del>,,</del>	
REASON FOR CHANGE		• .		·			•		
2968J/49				e noise immunit ause it is not		nter			1
NEW PURCHASE REQ'D.		SHOP R	EWORK RE	Q'D. 🛘	VENDOR	REWOR	K REQ	D. · · ·	
CUSTOMER ENGINEE  O IMMEDIATE CUST.  D CUST PER NEXT CALL  O INFORMATION ONLY  O NONE	RING     	ACKNO BY: DATE:_	OWLEDGE	DOCUM	TORY CHA ENTATION F MFG., CO	CHANG ST REDU	JCTION.		NG).
DISPOSITION	FINAL ASSY AREA	N RES	Outside 3	PRODU	CT IMPROV	EMENT.	•	: : :	125
SE AS IS TO REVIOUS REV.				FINAL APPROVAL				,: ·	1
O.CONFORM				APPROVED DESIGN ENGRG. APPROVED		•		•	<del></del>
O CONFORM IF NOT . EYOND OP! NATIONS . FFECTED				MFG. ENGRG.			<del></del>	•	. '



	- ;				·	
ASSEPELY PAR	PART NUPEER		LEGEND		۱. ۱	
ASSEMELY-DES		-PC4 -= 1.4 -5.2612S	SCL -CPU	–2÷– I.I Er–ras Ter – Ce-l Y–ceoeș–	.R-CE-L.YEGI	-+30
POSITION STRUCTURE	IN LEGENO	CCRFONENT PART NUMEER	CESCRIPTION	E C N	GUANTITY PER.ASSY	151
•	. I PI	775-0610-	10 PASAN LYNESTER	•	2.0000	. 4
1	NI	0-9	7406 HEX INV EUF CRIVERS HV	T EC9538		EACH
	·····	600	7425.2-4-IN-NGR-GATE	FAIREL	- 000	£7¢£
	2 ; H F	376-0093-	7432 4 2 IN GR GATE	PATREL -	1.0000	EACH
1	2n	10-	4LSOR 4'2 IN POS AND GATE	EC5805	<b>ာ</b> သ	FACE
	NT	76-015	741574.2.0 TYPE EDGE-TR		Ö	EAC
-	ж н	9	4LS155 2 2 4 LINE DECO		1.0000	EACH
		ę ·	C-72747-2-6EN-PURP.CSECPER.A		ن د	EAC!
<b>,</b>	2 2	276-0207 276-6219	. IC 74LS00 4 2 IN PCS NAND GATE	PATREL.	1.0000	FACT
•	Z	0	C 74LS374 & LATCHES W/TR ST	_	00	EACH
		4	74LS 244-OCIUAL-BUF /LINE-DR-3	17	939	EAC.
e4 *	Z :	376-0304	-K MASTER SLAVE	F/F FATREL	1.0000	EACH
	NI .	ઇ∵⊶	40 PIN SCCKET BURNDY # DILE24	0P1	2.0000	EAC
	121	7	PIN_SOCKET_EURNDY	FAIREL	000	TAC.
,	P FS 1	* 380-1001-4E	25 SIL CIOPE 36V, 100MA AT 1V	.4B EC9538	0000-9	EACH
		ti	-344607-70-V-20C-X4-S/6-S-		0.00	3
ed e	Z 2 H F		- C10 ZEN 18748 A 3.5V 400ML S C	0-7 FATREL	1.0000	E ACT
	   2       	( 1	314-5/6 12 SOL CPU		•	EACT
18d: 376	376-0138				1.0000	
300-	0/0/-		RAW MATERIAL MATA CVEPHEAD 10%	44.8320	1.0000	
300	300.1122		ILAGE . Empi tes	2.4658	1.000	0
300-	0-1390			51.7810-	1,0000	
			DIRECT LABOR	26.7879		
	•		TOTAL_COST	124.1683		

•:

•			•	•		•
IN: LEGENT	CCMPONENT	T.E.S.C.R.J.P.T	101.		ECN	QUANT 17
1 2 3						-PER- ASS
				-	•	"FUN NOO
00	00-0061	LARCO CLO CV	CTCUC			5 403
•		LABOR SUR-SYS	546 <b>45</b>			
	00-0011	Chopic done in		•	•	1.039
	0-1330=	CAR 330 PF 10%				1 . 0 0 6 :
IN 30	0-1680	CAF 680 PF 10%	500 V CERAM	IC CISC	EC9805	1.000
IN 30	0-1500	CAP 05 UF +86-	262 12 VCE	RAPIC D	EC9155	18.066
IN 30	10-1504		-20% 25 V CE		E11232	2.000
		CAF 001UF 10%				
	0-1910	CAP .0047 UF 20			CC-31 0t	
	·					2.000
		1 UF 50V -+80-2	OW CERAMIC	CAF (FIFRG -	FATREL	
	0-1531	1 LF CERAMIC CA	APACITER (HIG	H FREG)		5.000
IN 30	0-2147	CAP 047 - UF1	0%-100 V- MY	LAR	FATREL	2.000
IN 30	0-4004	CAP .15 UF 3	5 V 10% TAN'	TAXIAL		2.000
	0-4014	-CAP 2 . 2 UF 2	0. V 1 0 2 T. AN	T AX TAL		J. 0 0 C
	0-4.017		5 V 10% TAN			1.000
	0-4021	CAR-100.0UE1	5 V 10% TAN	. ~/ 1 / L		2 000
			0 V 10% TAN			
				· · - · —		2.000
		CAP1000FF.5%				
	1-0027		5 % QUARTZ			1.000
		SwiichSlice.se				
:P FS 331	0-1010-4E	RES 10 0h# 1/4	W 10% FIXED	CCYP I	11232	4.000
		RES100OHM_1/4				1-0.CC:
		RES 150 OFF 1/4			•	1.000
0 = 0 33(	0 2013 41.	_RES22GOb#_1/4	n 10% , 1850	CCKC E	70538	•
	•		• •			
· · · · · · · · · · · · · · · · · · ·	0-2033-4E					3.0004
		RES470CEK 1/41	-		~~~ ~~~~~	_
330	)-2056-4E	RES 560 CFF 1/41	# 10% FIXED	CCKP .		1.000
		_RES1KOHM-1//	14-10x-F1xED	COKEE	C9538	2 0 0 0 '
P FS. 330	-3022-48	RES 2.2K CFM 1/4	W 10% FIXED	COMP . P	ATREL	, 2.00C·
		_RES_4.7K.OHM_1/4				4. <del>23. 0.0</del> 0
	-3056-4E					1.066
		.RES8.2KCHM-1.44			C0155	1.000
•		RES 10K CFM 1/4			ATREL	
	-4010-4E					4.000
		RE-\$1 2K CHM1.∕-4				
P F S ' 330	-4015-4E	RES 15K OHM 1/4 _RES 18K:.Chm1/4	W 10% FIXED	COMP E	C9155	3.000
P FS	=4018=48=	_RES 18K:.Chm174	.W.1.0 %E.IXEO.	.CCKB E	C9155	1 . O C C (
P F S 330	-4022-48	RES 22K OFM 1/4 RES 33K CFM 1/4	W 10% FIXED	FILM P	ATREL	4.000:
. P. FS330.	= 4034=.4B= = =	RES33K_C+M.1/4	.W5 1E.IXED.			1. <b>.</b> 0 CC :
P F S 330	-4048-48	RES 47K CHM 1/4	U 5% FIXED	CCKB		2.0001
D F C 730	-F018-4F	RES 47K CFM 1/4 RES_180KChM_1/4	U 10% FIXED	COMB		1.666:
., F   J., 4		DEC	H 100 EIVED			1 0001
IN 331	-1022	RES 22 CHM 1/2 RES75 OHM1/8	M TOY LIVED	CUMP		1.000
IN 333	-0654==	-KES128	M X. 'E-TXFD	F.ILM		. 2.000:
IN 333	-0062	RES 249K CHM 1/ RES 4.7K CHM SIP	8W 1X FIXED	FILM		1.0001
	-0812	RES.4.7K.CHM.SIP	_2\PKG		ITREL	7. <u>.</u>
IN 336.	-1012	RES 50K CHM VAR	TRIM TOP AC	L RO EC	9155	1.0000
		RES . 100K . C.H VAR.				
		225-21021-110 PC				
		POLARIZING .KEYBI				
TN 275.	-0017	7518 283014 360M	U 40V SE NP	A S 52	·	1.000:
1N 375		TSTR 2N3014 360MI XSTR 2N2222A S.L.	MON TO-10	• ••		1 . 0 0 0 '
IN 3./ 2.	. 1 VE V		<del></del>			1.000
IN _ 3/5.	-1020	TRANSISTOR SPS65	51			
		TRANSIPADTO=18.				
`⊃N 376-	-0003	IC 7410N 3 3 IN 8	POS KAND GAT	L FA	IREL	1.000.

ARDWARE	CAN	MOT	CON	
AKDWAKE	しる	1401	COM	

### 2231W-1-2-3-6

279-5060-14 655-0167 465-0730 325-2417 VFU ASSEMBLY VFU TAPE RIBBON REED SWITCH HEAD CABLE		SOLENOID ASSY PAPER MARGIN KNOB SPROCKET BUSHING MAGNETIC PICK UP 279-5060-29 615-0376 279-0181 325-2416 420-1017
PCB DIFFERENCE 2	231W-1 10P 231W-2 12P	210-7060 210-6760
2231W-1 2231W-2 2231W-3 2231W-6	10P HEAD MODEL 61 12P HEAD MODEL 62 14.4P HEAD MODEL 63 12P HEAD MODEL 66	279-5060-22 279-5060-12 279-5060-59 279-5060-88
	MOTORS	

PAPER FEED MOTOR (VFU)	279-5060-37
SERVO DRIVE MOTOR 2231W-1	279-5060-15
SERVO DRIVE MOTOR 2231W-2-3	279-5060-16

### **PULLEYS**

ENCODER PICK UP - 10P	461-2021
ENCODER PICK UP - 12P	461-2020
ENCODER PICK UP - 14.4P	461-2027
PAPER DRIVE	449-0126
VERNIER SHAFT ASSY	279-5060-32
CLUSTED DITLEY ACCV 22214 2	270_5060_80

### **TRANSISTORS**

	NC 102 27E 102E	
HEAT SINK 2N HEAT SINK 2N HEAT SINK 2N HEAT SINK 2N HEAT SINK 2231W-6 2N HEAT SINK 2231W-6 2N	N6103 - 375-1035 N6292 - 375-1051 N6387 - 375-1052 N8203A - 375-1053 N4037 - 375-0018 N6107 - 375-1058 N6488 - 375-1054 N2906A - 375-1016	+ or - 17V SOLENOID DRIVER SOLENOID DRIVER + or - 18V CKT - 12V, - 17V CKT + 17V CKT + 5V CKT 5V DRIVER

### **DIODES**

H/S and POWER SUPPLY	1N4O3	380-4000
POWER SUPPLY RECTIFIER	· 1N4719	380-3002

### **CAPACITORS**


MOTHERBOA	ARD	
C1	14000MFD 12V	300-3045
C2-C4	12000MFD 25V	300-3073
C3-C5	7300MFD 40V	300-3074

Casten

### PRODUCT BULLETIN

NO.164

THE MODEL 2231W-6 LINE PRINTER



Wang Laboratories, Inc., announces a truly excellent addition to its family of matrix impact printers - The Model 2231W-6 Line Printer. The microprocessor controlled Model 2231W-6 represents a breakthrough in high-quality output from a matrix printer. By utilizing a high-density 12 x 20 dot matrix array, the Model 2231W-6 can deliver printed output that is practically indistinguishable from typewriter output (see sample below). This quality character registration is produced by impacting the dot matrix head twice at each character position. The first impaction forms the dotted character; the second impaction fills in the spaces between the dots.

### SAMPLE OUTPUT

The Model 2231W-6 Line Printer provides a high quality printed output to the System 2200. The printer uses a 12x20 dot matrix to print a full ASCII set of 96 characters containing both upper and lowercase letters, numbers and symbols, with rapid yet quiet operation.

The printer prints its full character set under program control, automatic formatting including both horizontal and vertical tabs is fully programmable to accommodate pre-printed and fixed-format output forms. An expanded character size (where dots of each character in the symbol matrix are each printed twice) is fully programmable to provide highlighted printing where desirable.

NO.164

The printer prints at a rate of 70 characters per second and can output 30 to 153 lines per minute depending on line length. It can print output up to 132 characters per line in a standard 12-pitch format. An expanded character size (dots of each character matrix are printed twice, horizontally) is fully programmable, providing highlighted output when desirable. The Model 2231W-6 prints an ASCII set of 96 characters containing both upper- and lowercase letters, numbers and symbols. The printer uses continuous form paper of widths from 3.5 in. (8.9 cm) to 13.5 in. (34.3 cm) edge-to-edge.

### WHAT ARE ITS SPECIAL FEATURES?

The Model 2231W-6 Line Printer provides full alphanumeric printing capability to the 2200 System. Its features include:

- . Typewriter-like registration
- . 132 characters per line
- . 12 x 20 dot matrix
- . 70 characters per second print speed
- . Full-line buffer
- . 96-character set, both upper- and lowercase characters
- . Audio alarm
- . Front-load and bottom-load paper feed
- . Character underscoring
- . Quarter-line feed
- . Line feed suppression
- Expanded print

2

NO. 164

### WHAT SWITCHES AND PANEL CONTROLS DOES IT HAVE?

The Model 2231W-6 control panel has a number of switches and indicators that make it easier to operate the printer:

- . ON/OFF switch (back of printer)
- . SELECT/deselect switch with status lamp
- . CLEAR switch to clear line buffer
- . LINE FEED switch
- . TOP-OF-FORM switch
- . FORMS OVERRIDE switch
- . Paper out indicator lamp
- . Power indicator lamp
- . Alarm lamp with one second audio tone

### WHAT FORMATS CAN IT PRINT?

Formats are fully programmable from the System 2200 with Wang BASIC statements such as PRINT, LIST, PRINT TAB, HEXPRINT, and PRINTUSING. In addition, all BASIC-2 output formatting instructions (such as LIST D, PRINT HEXOF) can be used with the 2200VP System. The Model 2231W-6 can have printed lines automatically formatted, and can use both horizontal and vertical tabs. Character underscoring is accomplished under program control at the same time the character is printed, thus removing the necessity for a separate head traverse. Expanded character size and line feed suppression are also programmable to highlight headings or important items. A programmable quarter-line feed feature can be used for printing subscripts or superscripts in equations or text.

### WHAT ARE THE PROGRAMMABLE CONTROL FUNCTIONS?

The Model 2231W-6 uses the following programmable control functions:

**FUNCTION** 

**DESCRIPTION** 

Line Feed

Advances paper one line (6 lines/in.).

Vertical Tab

Advances the paper the number of lines specified in the Vertical Tab code.

Form Feed

Advances the paper to the top of the

next form.

Carriage Return

Prints the current contents of the line buffer. An automatic line feed occurs after the line has been printed and the print head returns to the left side of

the printer carriage.

Expanded Character

Causes all subsequent characters on a line to be printed as expanded (double-

width) characters.

Quarter-line Feed

Advances paper one quarter of the standard 6 lines/in. line feed. It can be used when super or subscripting is

required. For example:

 $K_0 = - ((r_1 - r_2)s_x - (d_1 - d_2)s)^2$ 

Delete Printer Buffer

Clears buffer of a partial line.

Suppression of Line Feed

Suppresses the normal line feed. feature can be used for text highlighting or for inserting accent marks over characters. For example:

### SUPPRESSION OF LINE FEED

Audio Alarm

Generates an audible tone about one second in duration. This feature can

be used to alert the operator.

### WHAT IS THE COMPETITION?

With its very dense matrix, the Model 2231W-6 offers the customer the capability of using a dot matrix printer for his high-quality print applications. These applications have previously been dominated by the slower, more expensive solid font printers such as the IBM selectric, Typebar or Diablo daisy wheel printers. The Model 2231W-6 printer gives Wang a considerable competitive edge because of our lower price and higher speed. Also, add to this the inherent flexibility of the dot matrix printer with its comprehensive character set and double size print capability and you have an unbeatable combination. No longer need a customer have two printers, one for his high quality applications such as customer letters or policies, and one for his data processing work. The following table shows the salient features of the main competition and how the Model 2231W-6 compares to some low-cost, low-quality printers.

Characteristic	Wang 2231W-6*	Wang 228 1P*	Wang 2231W-2	H.P. 9871A*	IBM 5100	Terminent 1200*	Datapoint*	Centronios 701	DEC LA35
Speed	70cps	30cps Bidirectional	120cps	30cps Bidirectional	80cps Bidirectional	10-120cps	30cps Bidirectional	60cps	30cps
Number of Columns	1320 12-pitch	132@ 10-pitch 157@ 12-pitch	132	132	132	80/120	132	132	132
Font	12X20 Matrix	Daisy Wheel	7 X 9 Matrix	Solid Font	Matrix	Belt	Solid Font	5 % 7 Matrix	7 X 7 Matrix
Character Set	96	96	96	96	64 + apecials	94	96	64/128	96
Price	\$3,300	\$4,500	\$3,100	\$3,400	<b>\$3,975</b>	\$4,000	\$6,300	\$1,815**	\$2,260

HIGH QUALITY PRINT

<sup>\*\*</sup>OEM PRICES

	MODEL 2231W-6 Featu	ires	and Benefits
	FEATURES		BENEFITS
•	12 x 20 dot matrix, nominal	•	Quality characters are highly readable.
•	96 character set, ASCII	•	Both upper- and lowercase characters plus special symbols are available to support a wide variety of applications.
•	Up to 153 lines/min can be printed	•	Excellent performance in its price range.
•	Full-line buffer	•	CPU and printing operations can fully overlap to accelerate throughput.
•	Audio alarm	•	Alarm tone is programmable and can be used to warn operator of paper out condition.
•	Expanded print capability	• ,	Enlarged titles and headings for highlighting documents are programmable and easily produced.
•	Removable cartridge-ink ribbon	•	Snap-on cartridge-ribbon can be easily inserted and removed.
•	Deselection without data loss	•	Forms can be changed and aligned without losing data in the print buffer.
•	Front-load and bottom-load paper feed	•	Insertion of paper is handled quickly and easily.
•	Line feed suppression	•	Titles and a complete line of characters can be highlighted for special effects.
•	One-quarter line feed spacing	•	Superscripts and subscripts can be easily printed in equations or text.
	Character underscoring	· •	Characters can be underscored

as they are printed.

NO.164

### **SPECIFICATIONS**

Printer Size

Net Weight

60 lb (27 kg)

Speed

70 characters/sec, 30 to 153 lines/min

Character Configuration

12-pitch font: 12 x 20 dot matrix 24 x 20 dot matrix (for expanded print)

Character Set

ASCII 96 characters, both upper- and lowercase.

Line Width

132 characters, max (66 characters, expanded)

Line Density

6 lines/in. (nominal).

Ribbon

Cartridge - ink ribbon; endless, recirculating, Moebius loop.

Switches/lamps

ON/OFF, SELECT, LINE FEED, TOP-OF-FORM, CLEAR, FORMS OVERRIDE, paper out alarm and lamp, power on lamp, select lamp, and alarm tone.

### **PRODUCT BULLETIN** NO. 164

### Paper Size (edge-to-edge)

3.5 in. (8.9 cm) min, 13.5 in. (34.3 cm) max Paper width settings adjustable; up to four copies plus original can be printed.

### Vertical Format Control

Vertical Tab. Top-Of-Form (programmable)

### Programmable Operations

Audio Alarm Line Feed Vertical Tab Carriage Return Line Feed Suppression Form Feed Expanded Print Delete Buffer Quarter-Line Feed Underscore

### Cable

12 ft (3.66 m) cable with connector to the CPU.

### Controller

Standard Wang Printer Controller/CPU interface.

### Power Requirements

115 or 230 VAC + 10% 50 or 60 Hz + 1 Hz 1.25/0.65 amps, 150 watts

### **Fuses**

AC line:

1.5 amps (SB) for 115 VAC,

0.8 amps (SB) for 230 VAC

DC carriage motor: 2.5 amps (SB)

### Operating Environment

50° to 90°F (10° to 32°C)

20% to 80% relative humidity, allowable

35% to 65% recommended

#### Accessories

Optional stand

8



NO.164

Character Set and Expanded Print

1"#\$%&'()\*+,-./0123456789:; <=>?@

ABCDEFGHIJKLMNO PQRSTUVWXYZ[\]

^\_`abcdefghijklmnopqrstuvwxyz{|}~

### EXPANDED PRINT

### PRODUCT STATISTICS

Model Number	•	•	•	•	•	٠	•	٠	•	•	•	•			•	•	2231 <b>W-</b> 6
Part Number .	•	•	•	•	•		•	•		•		•	• -				177-2231W-6
Release	•		•				•			•	•	•	•	•	•	•	April 1, 1978
Available	•		•			•			•	•	•	•	٠	•	•	•	90 days ARO
Classification	n												٠				Mechanical